



*Quality aircraft since 1974*

## **SERVICE LETTER JUNE-15-01**

### **Issue Date**

Friday, June 15, 2001

### **Subject/Purpose**

This Service Letter defines the requirement to perform an on-going visual inspection for the purpose of locating leaks in the engine oil radiator system, as outlined in the Service Manual, Engine Group, number 22.

### **Affected Models**

The affected models are aircraft CH 2000 serial numbers 20-002 and up, using the oil cooler 20-M-36-2 (painted black)

### **Compliance Time**

Perform the instructions in this Service Letter at or before the next 50 hour inspection and every 50 hours after, as outlined in the Service Manual.

### **Inspection**

Visual Inspection of oil radiator. Check for oil leaking around oil radiator.

### **Repair if required**

Remove oil radiator and brackets and shroud and replace with new brackets 20-M-36-3 and new oil radiator part number 20-M-36-4 manufactured by Positech (gold), available from Zenair Ltd.

For additional information contact Zenair Ltd.

**ZENAIR LTD, HURONIA AIRPORT, MIDLAND, ONTARIO, CANADA L4R 4K8  
TEL:(705) 526-2871 - FAX:(705)526-8022**